



ABN 33 118 549 910

20 Walters Dr, Osborne Park, WA 6017
Locked Bag 13, Osborne Park, WA 6017
P +61 8 9329 3600 F +61 8 9329 3601

Thursday, January 5, 2023

Shire of Mingenew
21 Victoria Street,
Mingenew, Western Australia 6522

Attention: Maurice Battilana

Dear Maurice,

**RE: PLANNING APPLICATION FOR THE RIG SITE CAMP ASSOCIATED WITH THE ENERGY RESOURCES LIMITED
LOCKYER-3 EXPLORATION DRILLING PROGRAM**

Please find attached a planning application for the installation and operation of a rig camp site that will be utilized to support the upcoming Lockyer-3 exploration drilling program for Energy Resources Limited (ERL) within Petroleum Licence EP368 managed under the *Petroleum and Geothermal Energy Resources Act 1967*. The drilling activities are expected to commence in October 2023 although may be delayed until November 2023 based on potential variations to the current rig schedule.

Once drilling activities have commenced, they will be conducted continuously on 24-hour basis with two crews working back-to-back on 12-hour shifts. The rig site camp is planned to accommodate up to six (6) persons with an option for an additional two (2) persons, that are required on-site at the drilling rig for the duration of the drilling activity. There will be up to 22 additional non-accommodated personnel on site during each 12-hour shift.

The drilling program is temporary in nature and planned to be completed within 60 days for each well, however there may be a requirement (over a period of up to 2 years) for various short-term maintenance or well testing activities to be completed. These activities may require accommodation on site but would also be temporary in nature.

The rig site location map is provided as Attachment 1 and will be accessed via Burma Road and Strawberry North East Road (off Midlands Road). The rig site camp will be installed within the first five days of the drilling activity and will be conducted in conjunction with the installation of the drilling rig. The rig site equipment layout is provided as Attachment 2. The modular camp units will be transported to the site utilizing semi-trailers or winch trucks. Nine trailer loads will be required to transport the rig camp and associated equipment to the site.

The rig camp location is not within close proximity to any residential dwellings with the distance to the nearest residential dwelling being several kilometres. At the rig site camp, there will be no food preparation facilities (this will be conducted off site at the main camp).

The following information has been provided as attachments to the completed Development Application Form:

- ▶ Attachment 1: Site location showing the exploration well location with regards to the lot boundaries and lot area.
- ▶ Attachment 2: A site layout schematic that provides an indication of where the accommodation units will be situated with regards to additional key drilling rig infrastructure and wellsite boundaries.
- ▶ Attachment 3: A compilation of information regarding the rig site camp with plan views, dimensions and images associated with the temporary building structures.
- ▶ Attachment 4: The completed ATU applications, information and manual associated with the ATU system.

This information has been collated and submitted for and on behalf of Energy Resources Limited.


Yours sincerely,

Darrell Girgenti
Project Manager

Energy Resources Limited








Legend	
Lot/Plan Number	
<div></div>	P002983 M435
<div></div>	P002984 M428
<div></div>	P002984 M433
<div></div>	P008112 5
<div></div>	P108088 2385
<div></div>	Camp Location
<div></div>	Proposed Well Locations
<div></div>	WA State Detailed Roads

LOCKYER-3 SITE LAYOUT


Operator	Energy Resources Ltd		Permit	EP368	Location	Onshore Perth Basin, WA		
Surface Location					Water Bore			
Latitude	29° 10' 13.10"S	Longitude	115° 15' 33.64"E		Latitude	29° 10' 13.68"S	Longitude	115° 15' 30.66"E
	Revision		Rev C		Date		14/11/2022	
	Drafted		Darrell Girgenti		Position		Project Manager	
	Signed							
	Reviewed				Position			
	Signed							




Required Soil Bearing Minimum Capacity (Graded and Compacted Area)


HIGH LOAD BEARING GRADED AND COMPACTED AREA (MIN 250kPA/36psi)

SHEETED, GRADED AND COMPACTED AREA W/ 2% FALL (MIN 120kPA/18psi)







ELEVATION 1




ELEVATION 3




ELEVATION 2



ELEVATION 4




FLOOR PLAN



SECTION A-A

SCALE 1:20



90 X 70 BLOCK

SCALE 1:10

ITEM:	DESCRIPTION:	QTY:
W1.	1029H. X 1210W. HORIZONTAL SLIDING WINDOW (6.38 LAMINATED - GREY)	3.
D1.	2040H. X 820W. METAL CLAD REBATE EDGE EXTERNAL DOOR C/W SPRING RESTRAINER & EXIT SIGN.	2.
D2.	2040H. X 720W. S.P.M. HOLLOW CORE INTERNAL DOOR C/W EXIT SIGN AND DOOR CATCHES TOP AND BOTTOM.	4.
1.	SPLIT R/CYCLE A/C.	3.
2.	TOILET SUITE.	2.
3.	TOILET ROLL HOLDER.	2.
4.	500MM X 400MM HAND BASIN C/W MIRROR OVER.	2.
5.	1055MM X 945MM F/GLASS SHOWER CUBICLE C/W SHOWER CURTAIN.	2.
6.	WALL MOUNTED EXHAUST FAN.	2.
7.	1200MM X 750MM DESK C/W PLASTIC STACK CHAIR.	3.
8.	KING SINGLE BED C/W STORAGE DRAWERS.	3.
9.	LOCKER.	3.
10.	250L ELECTRIC HOT WATER SERVICE.	1.
11.	BAR FRIDGE	3.
12.	COAT HOOKS.	3.
13.	15 AMP ISOLATOR.	3.
14.	SINGLE GPO.	2.
15.	DOUBLE GPO (100 A.F.F.L.)	9.
16.	LIGHT SWITCH.	6.
17.	FLUORESCENT BED LIGHT.	3.
18.	DATA POINT.	3.
19.	BATTEN CEILING LIGHT	4.
20.	BATTEN CEILING LIGHT C/W BATTERY BACKUP.	2.
21.	1 X 36W FLOURO. VANDALITE @ 2400 HEIGHT C/W BATTERY BACKUP & PE CELL.	2.
22.	SMOKE DETECTOR.	3.
23.	WILCO 5 PIN MALE PLUG FOR GENERATOR CONNECTION.	1.
24.	CIRCUIT BREAKER BOARD (3 PHASE).	1.

NOTE:

- ALL DOORS TO HAVE STICK ON REFLECTIVE EXIT SIGNS ON INSIDE FACE OF DOOR.
- ALL EXTERNAL LIGHTS TO BE ON SAME P.E. CELL.

CLIENT: ENSIGN INTERNATIONAL

SALES ORDER NO: -

PROJECT: 12.0M X 2.9M
3 PERSON LIVING QUARTERS

SERIAL NO: -


SITE: EX PLANT

EMAC
S Y S T E M S


KARYDAV PTY. LTD. A.C.N. 061 115 133
1253 MAIN NORTH ROAD, PARA HILLS WEST,
SOUTH AUSTRALIA 5096
P.O. BOX 46, PARA HILLS
PH: (08) 8260 4866 FAX: (08) 8349 6273
BUILDERS LICENCE NO. GL 102757

SUBMITTAL STATUS	INITIAL	DATE
A CONTRACT DRAWINGS		
B BILL OF MATERIALS		
C ISSUE FOR PURCHASING		
D ISSUE FOR PRODUCTION		
E RELEASE FOR DELIVERY		
F APPROVED BY MANAGER		


DWG NO: 3 PERS LQ	SHEET: 1 OF 1
SCALE: 1:100	DATE: 5/03/10
DRAWN: JR	CHECK: TS
REV	6




ELEVATION 1




ELEVATION 3




ELEVATION 2



ELEVATION 4




FLOOR PLAN



ITEM:	DESCRIPTION:	QTY:
W1.	1029H. X 1210W. HORIZONTAL SLIDING WINDOW (6.38MM LAMINATE - GREY)	3.
D1.	2040H. X 820W. METAL CLAD REBATE EDGE EXTERNAL DOOR C/W SPRING RESTRAINER & EXIT SIGN.	3.
1.	SPLIT R/CYCLE A/C.	3.
2.	FULL WALL 750MM DEEP DESK.	5.
3.	BOOK SHELF OVER DESK C/W BRACKETS UNDER.	2.
4.	4 DRAW FILING CABINET.	5.
5.	TYPIST CHAIR WITH ARMS.	3.
6.	TYPIST CHAIR NO ARMS.	3.
7.	1000H X 1500W WHITEBOARD	3.
	15 AMP ISOLATOR.	3.
	DOUBLE GPO.	12.
	LIGHT SWITCH.	3.
	DATA POINT.	6.
	2 X 36W. DIFFUSED FLUORO C/W BATTERY BACKUP.	3.
	1 X 36W FLOURO. VANDALITE @ 2400 HEIGHT C/W BATTERY BACKUP & PE CELL.	2.
	SMOKE DETECTOR.	3.
	WILCO 5 PIN MALE PLUG FOR GENERATOR CONNECTION.	1.
	CIRCUIT BREAKER BOARD (3 PHASE).	1.

NOTE:

- ALL DOORS TO HAVE STICK ON REFLECTIVE EXIT SIGNS ON INSIDE FACE OF DOOR.
- ALL EXTERNAL LIGHTS TO BE ON SAME P.E. CELL.



90 X 70 BLOCK

SCALE 1:10

SUBMITTAL STATUS	INITIAL	DATE
A CONTRACT DRAWINGS		
B BILL OF MATERIALS		
C ISSUE FOR PURCHASING		
D ISSUE FOR PRODUCTION		
E RELEASE FOR DELIVERY		
F APPROVED BY MANAGER		

CLIENT: ENSIGN INTERNATIONAL

SALES ORDER NO: -

PROJECT: 12.0M X 2.9M 3 ROOM OFFICE

SERIAL NO: -


SITE: EX PLANT

EMAC


S Y S T E M S

KARYDAV PTY. LTD. A.C.N. 061 115 133
1253 MAIN NORTH ROAD, PARA HILLS WEST,
SOUTH AUSTRALIA 5096
P.O. BOX 46, PARA HILLS
PH: (08) 8260 4866 FAX: (08) 8349 6273
BUILDERS LICENCE NO. GL 102757


DWG NO: 3 RM OFF	SHEET: 1 OF 1
SCALE: 1:100	DATE: 5/03/10
DRAWN: JR	CHECK: TS
REV	0




ELEVATION 1



ELEVATION 2




ELEVATION 4



ELEVATION 3


NOTE:

1. ALL EXTERNAL DOORS TO HAVE STICK ON REFLECTIVE EXIT SIGNS ON INSIDE FACE OF DOOR.
2. ALL EXTERNAL LIGHTS TO BE ON SAME P.E. CELL.




SECTION A-A

SCALE 1:20



90 X 70 BLOCK

SCALE 1:10



FLOOR PLAN

ITEM:	DESCRIPTION:	QTY:
W1.	1029H. X 1210W. HORIZONTAL SLIDING WINDOW (6.38 LAMINATED - GREY)	2.
W2.	350H. X 750W. ALUMINIUM SLIDING WINDOW. (OBSCURE GLAZING)	2.
D1.	2040H. X 820W. METAL CLAD REBATE EDGE EXTERNAL DOOR C/W SPRING RESTRAINER & EXIT SIGN.	4.
1.	SPLIT R/CYCLE A/C.	2.
2.	TOILET SUITE.	2.
3.	TOILET ROLL HOLDER.	2.
4.	500MM X 400MM HAND BASIN C/W MIRROR OVER.	2.
5.	WALL MOUNTED EXHAUST FAN.	2.
6.	4 DRAW FILING CABINET.	2.
7.	750MM DEEP DESK UNIT C/W CABLE ACCESS HOLES.	1.
8.	SHELVING OVER DESK (AS PER DETAIL).	1.
9.	COAT HOOKS.	12.
10.	LAMINATED CUPBOARD UNIT.	1.
11.	900MM S/STEEL INSET SINGLE BOWL SINK.	1.
12.	CHILLER/BOILER UNIT.	1.
13.	380L FRIDGE.	1.
14.	TABLE AND BENCHES (SCREWED TO FLOOR).	2.
15.	FIRST AID BOX.	1.
16.	1000 X 1800 WHITE BOARD.	1.
17.	1000 X 2400 WHITE BOARD.	1.
18.	50L UNDERBENCH HOT WATER UNIT.	1.
19.	CLERICAL CHAIR.	2.
▲	15 AMP ISOLATOR.	2
△	SINGLE GPO.	3.
△	DOUBLE GPO (100 A.F.F.L.)	6.
×	LIGHT SWITCH.	4.
⊕	BATTEN CEILING LIGHT	2.
=====	2 X 36W. DIFFUSED FLUORO.	3.
=====	2 X 36W. DIFFUSED FLUORO C/W BATTERY BACKUP.	2.
⊕	1 X 36W FLOURO. VANDALITE @ 2400 HEIGHT C/W BATTERY BACKUP & PE CELL.	2.
○	SMOKE DETECTOR.	2.
⊕	ELECTRICAL POINT OF ENTRY (TBA).	1.
⊕	CIRCUIT BREAKER BOARD (3 PHASE).	1.

SUBMITTAL STATUS	INITIAL	DATE
A CONTRACT DRAWINGS		
B BILL OF MATERIALS		
C ISSUE FOR PURCHASING		
D ISSUE FOR PRODUCTION		
E RELEASE FOR DELIVERY		
F APPROVED BY MANAGER		

CLIENT: ENSIGN INTERNATIONAL

SALES ORDER NO: -

PROJECT: 12.0M X 2.9M OFFICE/TOILET/LUNCHROOM

SERIAL NO: -

SITE: -

EMAC
S Y S T E M S

KARYDAV PTY. LTD. A.C.N. 061 115 133
1253 MAIN NORTH ROAD, PARA HILLS WEST,
SOUTH AUSTRALIA 5096
P.O. BOX 46, PARA HILLS
PH: (08) 8260 4866 FAX: (08) 8349 6273
BUILDERS LICENCE NO. GL 102757

DWG NO: OFF/TOI/LNCH	SHEET: 1 OF 1
SCALE: 1:100	DATE: 5/03/10
DRAWN: JR	CHECK: TS
REV	0

CERTIFIED
A. PRESCOTT
RP-16002

A. Prescott
REF: 1235



Proudly owned, designed and manufactured
by Suncoast Waste Water Management

Technical Specifications

OZZI KLEEN Sewage Treatment Systems

SK20A-G



Efficiency, Reliability, Simplicity
www.ozzikleen.com

1. DESIGN CAPACITY

The design capacity of the SK20A-G treatment plant is 4,000L per day, producing advanced secondary effluent quality as specified below.

2. DESIGN PARAMETERS

The performance of the OZZI KLEEN SK20A-G Sewage Treatment Plant will achieve advanced effluent quality provided the incoming wastewater parameters meet the following characteristics:

Sewage Inlet

Parameter	Unit	Influent	Advanced
Biological Oxygen Demand (BOD ₅)	mg/L	≤ 350	≤ 10
Total Suspended Solids (TSS)	mg/L	≤ 350	≤ 10
Total Nitrogen	mg/L	≤ 75	≤ 10
Total Phosphorus	mg/L	≤ 15	≤ 5
Faecal Coliforms, FC	cfu/100 mL	-	≤ 10
Chlorine Residual	mg/L	-	0.5 ≤ 2.0
pH		6.0 ≤ 8.5	6.0 ≤ 8.5

3. SERVICE LIFE

The Ozzi Kleen SK20A-G was designed for a minimum service life of 15 years

4. ENGINEERING CALCULATION AND POE

Description	Document No.	Revision
SK20A-G Design Calculation Sheet	OK-SK20A-G-CS	12/11/2020
SK20A-G Power & Operating Cost Estimate	OK-SK20A-G-POE	12/11/2020
SK20A-G Elevation View Drawing	GD-SK20A-G-H06	17/11/2020
SK20A-G Plan View Drawing	GD-SK20A-G-H05	17/11/2020

CERTIFIED
A. PRESCOTT
RP-16002

AP
REF: 1235

Suncoast Waste Water Management

Plant Engineering Calculation

Project: Ozzi Kleen SK20A-G

Model	Unit	SK20A-G	Notes
1. Process Design Parameters			
Plant Capacity	EP	20	
Hydraulic flow	l/day	4000	
BOD ₅ loading	mg/l	350	
BOD ₅ loading	kg/day	1.4	
Suspended solids loading	mg/l	350	
Suspended solids loading	kg/day	1.4	
Mixed Liquor Suspended Solids (MLSS)	mg/l	5000	Typical extended aeration: 2500 to 6000 mg/l
Sludge Age	days	40	Typical extended aeration: > 30 days
Flow hours per day - Hydraulic sizing	hr/day	24	
Blower on time per cycle	min	60	
Settling time per cycle	min	30	
Decant time per cycle	min	30	
Total cycle time	min	120	
Number of cycles per day	cycles	12	
Total decanting time per day	min	360	
Total decanting time per day	hr	6	
Total aeration time per day	min	720	
Total aeration time per day	hr	12	
2. Aeration Tank			
Number of Aeration Tanks		2	Two RP Tanks, SBR operation
Aeration Tank outside diameter	mm	1900	
Shell Thickness	mm	18	
Aeration Tank inside diameter	mm	1864	
Aeration Tank top water level	mm	1745	
Aeration Tank volume - actual, calculated	litre	8,414	Excluding 4 x ø450 OD tubes volume
Aeration Tank volume per EP actual		421	
Maximum decant depth	mm	150	
Aeration Tank max. decant volume	litre	723	
Max. decant volume to daily flow	%	18%	Two cells on same cycling
Aeration Tank minimum working volume	litre	7690	
Max. decant ratio	%	8.6%	
Hydraulic Residence Time based on TWL	hr	50	24 hours minimum: Ref: SA Dept. of Health
Hydraulic Residence Time based on BWL	hr	46	
Food to Microbial Mass ratio (F:M Ratio)	g/g day	0.033	Typical for extended aeration, F:M 0.04 to 0.15
3. Air Flow			
Oxygen demand (kg O ₂ / kg BOD ₅)	kg/kg	2.4	Ref: SA Dept. of Health
BOD ₅ loading	kg/day	1.40	
Actual Oxygen demand required	kg O ₂ /day	3.4	Ref: SA Dept. of Health
1 kmol of air at STP occupies:	m ³ /kmol	22.41	
1 kmol of dry air has mass of:	kg/kmol	28.96	
Gravimetric fraction of Oxygen in dry air	kg/kg	0.2314	
Mass of Oxygen per kmol of air	kg/kmol	6.701	
Mass of Oxygen per m ³ of air at STP (dry basis)	kg/m ³	0.299	
Inlet air temperature	°C	25	25°C default
Inlet air relative humidity	%	70	
Inlet air temperature	K	298.15	
Standard air temperature	°C	0	
Standard air temperature	K	273.15	
Inlet air pressure	bara	1.013	
Saturated vapour pressure at inlet conditions	bara	0.032	0.03166 for 25°C. 0.04242 for 30°C

CERTIFIED
A. PRESCOTT
RP-16002

ARP
REF: 1235

Blower discharge pressure at TWL	mbar	207	2 Blowers	
Blower air flow (FAD) - actual	m³/hr	18		
Blower model	LP150HN			
Number of Elastox-T type B diffusers		4		
Air flow per diffuser (FAD at suction temperature)	m³/hr	4.50	Recommended for Elastox-T: 2 to 6 Nm³/h	
Ratio : Actual m³ (wet basis) per Nm³ (dry basis)		1.116		
Air flow per diffuser (at STP)	Nm³/hr	4.03		
Elastox-T diffuser Oxygen transfer (from	g O₂/m Nm³	22		
Diffuser immersion depth at TWL	m	1.545		
Diffuser Oxygen transfer at immersion depth	g O₂/Nm³	33.99		
Oxygen transfer per diffuser	g O₂/hr	137.06		
Oxygen transfer, all diffusers	kg O₂/hr	0.55		
Oxygen transfer, all diffusers - daily basis at TWL	kg O₂/day	6.6		
Standard Oxygen transfer efficiency (wet basis)	%	12.7		
4. Chlorine Contact Tank				
Decanting flow rate	l/min	16	Based on average flow plus 40% margin	
Decanting flow rate	m³/hr	0.9		
Minimum Cl contact time	min	30		
Minimum Cl contact tank volume required	litre	467		
Number of Contact Tanks		2		
Contact Tank outside diameter	mm	450		
Shell Thickness	mm	10		
Contact Tank inside diameter	mm	430		
Contact Tank top water level	mm	1745		
Contact Tank volume - calculated	litre	507		
Cl contact time - actual	min	33		
Chlorine tablet consumption				
dosage rate	mg/L	10		
daily tablet consumption	kg/d	0.04		
min. storage - 3 months	kg	3.64		
number of tablets (200 g/ea) - 3 months	no.	18		
5. Waste Sludge Tank				
Sludge oxidation ratio	40 l	40		
Sludge D.S. wastage based on SS loading	kg/day	0.035		
Wet sludge solids content in sludge tank	% D S	1		
Wet sludge mass to be wasted	kg/day	3.5		
Wet sludge volume wasted where SG = 1	l/day	3.5		
Period between tank de-sludging	day	90		
Minimum sludge tank volume required	litre	315		
Number of Sludge Tanks		2		
Sludge Tank outside diameter	mm	450		
Shell Thickness	mm	10		
Sludge Tank inside diameter	mm	430		
Sludge Tank top water level	mm	1900		
Sludge Tank volume - calculated	litre	552		
Period between de-sludging - actual	day	158		
6. Alum Dosing System (SK20A / A-G ONLY)				
Dosage rate	mg/L	30		
Daily alum consumption	kg/d	0.12		
Percentage of alum solution	%	20		
Daily alum consumption at 20% solution:	kg/d	0.6		
Daily alum consumption at 20% solution:	L/d	0.53		
Dosing rate per inflow at 20% solution	ml/m³	133		
Chemical tank volume	litre	80		
Minimum refill period of Alum	days	150		

CERTIFIED
A. PRESCOTT
RP-16002

ARP
REF: 1235

Suncoast Waste Water Management

AWTS Process Design Parameters for Power Utilisation


Project: Ozzi Kleen SK20A-G

Design Parameter	EP	20				
Hydraulic Flow	l/day	4000				
Flow Hours per Day - Hydraulic Sizing	hr/day	24				
Blower ON Time per Cycle	min	60				
Settling Time per Cycle	min	30				
Decant Time per Cycle	min	30				
Total Cycle Time	min	120				
Number of Cycles per Day	cycles	12	Model			
Transfer Pump Flow Rate	l/min	200	Showfou STA-112			
Effluent Pump Flow Rate	l/min	100	Reefe RVS300			
Grease Trap Pump Flow Rate (SK20G / A-G ONLY)	l/min	200	Reefe RVS300			
Dosing Pump Flow Rate (SK20A / A-G ONLY)	l/hr	3	Iwaki EJ B16			
Air Blower	m³/hr	18	Thomas LP150HN			
Power Utilisation Based on Rated Power	Installed Power		Unit	Hrs/day	Energy Used	
	3 phase	1 phase		hr	kWh	
Transfer Pump		0.75	kW	0.33	0.25	
Effluent Pump 1		0.40	kW	0.33	0.13	
Effluent Pump 2		0.40	kW	0.33	0.13	
Grease Trap Pump (SK20G / A-G ONLY)		0.18	kW	0.11	0.02	
Dosing Pump (SK20A / A-G ONLY)		0.10	kW	0.37	0.04	
Blower 1		0.13	kW	12.00	1.56	
Blower 2		0.13	kW	12.00	1.56	
Control System		0.10	kW	24.00	2.40	
Total Installed Power	0.00	2.19	kW		6.1	
Average Power			kW		0.25	
Current Draw Based on Full Load Current	Full Load Current		Unit	Hrs/day	Amp-hr Used	
	3 phase	1 phase			3 phase	1 phase
Transfer Pump		6.00	A	0.33		2.00
Effluent Pump 1		4.00	A	0.33		1.33
Effluent Pump 2		4.00	A	0.33		1.33
Grease Trap Pump (SK20G / A-G ONLY)		4.00	A	0.11		0.44
Dosing Pump (SK20A / A-G ONLY)		0.50	A	0.37		0.19
Blower 1		0.85	A	12.00		10.20
Blower 2		0.85	A	12.00		10.20
Control System		1.00	A	24.00		24.00
Total Installed Current	0.00	21.20	A		0.00	49.69
Average Current			A		0.00	2.07

Operating Cost Estimating	unit	unit price	qty/d	qty/yr	\$/yr
Power	kW	0.20	6.1	2224	445
Chlorine	kg	12.50	0.04	15	183
Alum	kg	1.50	0.12	44	66
Waste Sludge Disposal	L	0.20	3.50	1278	256
total:	\$/year				949
Note: All costs are estimated based on the SK20A-G operating for 365 days at full design capacity (4 kL/day), an adjustment should be made when less sewage is treated per year.					

CERTIFIED
A. PRESCOTT
RP-16002


ARP
REF: 1235



**CERTIFIED
A. PRESCOTT
RP-16002**

ARP
REF: 1235

<div> </div>	Suncoast Waste Water Management		DWG NO. GD--SK20A--G-H05		SCALE NTS	
	CLIENT GENERAL		PROJECT OZZI KLEEN SK20A--G AWTS		DATE 17/11/20	
	59 INDUSTRIAL AVE KUNDA PARK QLD 4556 PH +61 7 5455 4900 FAX +61 7 5456 4677 www.ozzikleen.com		TITLE PLAN VIEW		DESIGN AP	
	17/11/20 TANK DIMENSIONS ADDED		2 YH		DRAWN YH	
26/10/16 GENERAL REVISION		1 YH			CHKD SB	
DATE	DESCRIPTION	REV	BY			



CERTIFIED
A. PRESCOTT
RP-16002

ARP
REF: 1235

 <div>Suncoast Waste Water Management</div>				59 INDUSTRIAL AVE KUNDA PARK QLD 4556 PH +61 7 5459 4800 FAX +61 7 5456 4877 www.ozzikleen.com		CLIENT	GENERAL DRAWING		DESIGN	AP	
				PROJECT		OZZI KLEEN SK20A-G AWTS		DRAWN	YH		
				TITLE		ELEVATION VIEW		CHKD	SB		
								DATE	17/11/20		
17/11/20	TANK WATER LEVEL INDICATED	2	YH								
26/10/16	GENERAL REVISION	1	YH								
DATE	DESCRIPTION	REV.	BY								
DWG NO. GD-SK20A-G-H06										SCALE	NTS

31 May 2021

Aztech Well Construction
3/1138 Hay St,
West Perth
WA 6005

Job No: 21FCE026
Your Job:

Att: Mr Darrell Girgenti

Dear Darrell

Project: Temporary Transportable Accommodation Buildings to be Located at the Shire of Mingenew

Building Tie Down Certification

Introduction

Aztech Well Construction (Aztech) plan to install two 3-person sleeper transportable buildings at Energy Resources new drill camp which will be situated in the Shire of Mingenew. Aztech have requested Flow Consulting Engineers (FCE) to design check the tie down requirements for the two buildings being installed in accordance with current relevant Australian Design Standards. Aztech have advised that the camp will be installed for the duration of drilling activities, which at this stage is planned for a maximum of 2 months.

Description of Structures

The 2 transportable buildings are of similar construction and have been manufactured by EMAC Systems in South Australia. The buildings are 12m long x 2.9m wide x 2.6m high. Aztech have advised that the self-weight of each building is 15 Tonnes. A letter from EMAC is provided in Appendix B which says that the transportable buildings have been fabricated for the appropriate wind region for the proposed installation location.

Calculations

In accordance with AS1170.2 the tie down for each transportable accommodation building has been checked for the following requirements:

1. Region B: Mingenew. The Terrain Category at the site has been taken as 2. Importance level 2. Ultimate wind speed 53m/s (190.8km/hr).
2. In accordance with the proposed installation time, the annual probability of exceedance of the wind event has been calculated as 1:250.
3. The self-weight of each transportable accommodation building has been taken 15 Tonnes.
4. The transportable buildings shall be located on a 300mm thick pad of compacted gravel.

5. The static friction coefficient between the accommodation building steel bases and the gravel ground has been taken as $\mu = 0.35$.

Results & Recommendations

Calculations to determine building sliding and overturning under wind load indicate that the buildings shown on Drawing No 3 PERS LQ provided in Appendix A will be stable under their self-weight and will not require additional tie-down.

To ensure that the buildings remain well supported by the compacted gravel surface beneath the buildings, the soil moisture content of the foundation material under the buildings is required to be kept dry. Surface drainage shall be designed and constructed to avoid water ponding against or near buildings. The ground in the immediate vicinity of the building perimeters is recommended to be graded to fall 50 mm minimum away from the building over a distance of 3m and shaped to prevent ponding of water near the buildings.

Trusting that this meets with your requirements, should you have any further queries, please do not hesitate to contact the undersigned on (08) 9964 5459.

Yours faithfully

A handwritten signature in black ink, appearing to be 'Lester Smith', written in a cursive style.

Lester Smith

Engineering Manager

Attached: Appendix A & B.

CLIENT: ENSIGN INTERNATIONAL	PROJECT: 12.0M X 2.9M 3 PERSON LIVING QUARTERS	SITE: EX PLANT	DWG NO: 3 PERS LQ	SHEET: 1 OF 1
SALES ORDER NO: -	SERIAL NO: -		SCALE: 1:100	DATE: 5/03/10
			TRAINING: JR	CHKD: TS
			REV: 6	

Appendix B: Building Design Certification.



General Builders Licence No. BLD 102757

KARYDAV PTY. LTD. A.C.N.061 115 133
HEAD OFFICE: 1253 MAIN NORTH ROAD
PARA HILLS WEST, SOUTH AUSTRALIA
POSTAL ADDRESS: PO BOX 46, PARA HILLS 5096
TEL: (08) 8260 4866 FAX: (08) 8349 6273

MANUFACTURERS OF QUALITY TRANSPORTABLE ACCOMMODATION

1st April 2015

Ensign Australia
15-17 Westport Road
Edinburgh North SA 5113

Mark Tonin,

Re: Rig Camp Buildings

Confirmation that Buildings have been constructed to W41N Classification in accordance with AS4055

Claude Bagnara
Commercial Manager, Design & Construction
EMAC Systembuilt Group
1253 Main North Road
Para Hills West SA 5096
Ph: 1300 073 995
Fax: (08) 8349 6273
M: 0419 826 821
systembuiltthomes.com.au
emacmodular.com.au
lowriemodular.com.au

**EmacSystembuilt
Group**

systembuilt
designed for living

EMAC
modular

LOWRIE
QUALITY TRANSPORTABLE ACCOMMODATION